
Kayak Pool Installation Manual

Kayak Pool Installation Manual

*Downloaded from everybodystreet.com
by Goodman & Dudley*

YOUR COMPLETE GUIDE TO A SUCCESSFUL KAYAK POOL INSTALLATION

Installing an above-ground pool can transform your backyard into a personal oasis, offering countless hours of relaxation and family fun. Among the most popular choices on the market today is the kayak pool, renowned for its robust construction, elegant appearance, and relative ease of assembly. However, while a kayak pool installation is more straightforward than an in-ground build, it is still a substantial project that demands careful planning, the right tools, and a methodical approach. A successful installation hinges on understanding every step, from selecting the perfect spot to the final fill of water. This comprehensive kayak pool installation manual is designed to guide you through the entire process, ensuring you avoid common pitfalls and end up with a safe, level, and long-lasting pool that your family will enjoy for years to come.

Whether you are a first-time pool owner or have some experience with above-ground setups, this guide provides the detailed, actionable information you need. We will cover ground preparation, base materials, the step-by-step assembly of the

pool wall and liner, plumbing connections, and essential maintenance tips. By following this manual closely, you will not only ensure a smooth installation but also protect your warranty and maximize the lifespan of your investment. Let us dive into the foundational work that sets the stage for a flawless kayak pool installation.

PRE-INSTALLATION PLANNING AND SITE SELECTION

Before you even open the box containing your new kayak pool, careful planning is essential. The longevity and stability of your pool depend significantly on the site you choose. This section of the kayak pool installation manual outlines the critical factors to consider when selecting and preparing your location.

Choosing the Ideal Location

The location of your kayak pool directly impacts its structural integrity and the enjoyment you get from it. Consider these key points when surveying your yard:

- **Level Ground is Non-Negotiable:** The single most important factor is a completely level surface. Even a slight slope of one or two inches can cause immense pressure on

the pool wall, leading to bulging, warping, or a catastrophic collapse. Use a long level or a laser level to check the area in multiple directions.

- **Access to Utilities:** Choose a location away from overhead power lines, underground gas lines, sewer lines, and sprinkler systems. Contact your local utility marking service before you dig to ensure it is safe.
- **Sunlight and Wind:** Position the pool to receive maximum sunlight throughout the day, which helps keep the water warm naturally. Avoid areas that are excessively windy, which can increase evaporation and cooling. A nearby fence, hedge, or building can provide a windbreak.
- **Proximity to the House:** While you want the pool close to the house for convenience and supervision, ensure you are not too close to the foundation. Local building codes often require a minimum distance (typically 5 to 10 feet). A closer location also makes running electricity for a pump and filter easier.
- **Clearance from Trees:** Avoid placing your kayak pool directly under trees. Falling leaves, seeds, and branches create a constant mess. More importantly, tree roots can grow and disrupt your level base over time, and falling limbs can damage the pool liner.
- **Drainage Considerations:** Do not install your pool in a low spot where rainwater naturally collects. Proper drainage away from the pool area is vital to prevent the ground from becoming soft and unstable around the pool walls.

ESSENTIAL TOOLS AND MATERIALS FOR INSTALLATION

Having all the necessary tools and materials ready before you start will save you time and frustration. While your kayak pool kit will include the major components like the steel wall, liner, top rails, and uprights, you will need additional items for the base and assembly. This kayak pool installation manual recommends gathering the following:

- **For Ground Preparation:** Shovel, rake, wheelbarrow, long 2x4 or screed board, carpenter's level (minimum 4 feet long), tape measure, string line, utility knife, and a hand tamper or plate compactor.
- **For Base Material:** Masonry sand or stone dust, a roll of pool underlayment or floor foam (often sold separately), and optionally, a layer of weed barrier fabric.
- **For Assembly:** A power drill with Phillips and flathead bits, a rubber mallet, a socket set or adjustable wrench, a utility knife with extra blades, duct tape, and a pair of sturdy scissors. A second or third person is indispensable for lifting the wall and holding parts.
- **For Plumbing and Electrical:** Teflon tape for threaded connections, a utility knife for cutting hoses, hose clamps, and any specific adapters required to connect your pump and filter. Ensure you have a GFCI-protected outdoor electrical outlet nearby.

STEP-BY-STEP KAYAK POOL INSTALLATION PROCESS

With your site chosen and tools ready, you are now ready for the main event. Follow these steps carefully, consulting your specific kayak pool model's instructions for any minor variations. This section of the kayak pool installation manual provides a general overview that applies to most major brands.

Step 1: Marking and Excavating the Area

Begin by marking the exact circumference of your pool. Drive a stake into the center of your chosen location. Tie a string to the stake that is exactly half the diameter of your pool (the radius) plus an extra six inches. Use this string to draw a circle in the soil with marking paint or a stick. The extra six inches provides working room for the wall and allows space for the sand collar you will create later.

Now, remove all grass, sod, rocks, roots, and debris within this circle. You need to excavate the entire area to a depth of about two to three inches. The goal is to remove the topsoil and organic material to create a stable, non-compressible base. If you are dealing with a sloped area, you will need to dig into the high side to create a level plane. Do not add fill dirt to the low side, as it will eventually settle and compromise the level.

Step 2: Creating a Perfectly Level Base

This is the most critical step in the entire **kayak pool installation manual**. An unlevel base is the primary cause of pool failure. Start by adding a layer of masonry sand or stone dust (about one to two inches deep) over the excavated area. Do not use play sand or beach sand, as the grains are too round and will not compact well. Use a long 2x4 board as a screed to drag the sand flat, using the cut edges of the excavation as your guide for depth.

To verify level, place your long level on the 2x4 and check in multiple directions across the entire circle. Adjust by adding or removing sand in low or high spots. Once the sand is roughly level, use a hand tamper or plate compactor to compact it firmly. After compaction, check the level again and make fine adjustments. The final surface should be perfectly flat, level to within one-quarter of an inch, and firm enough that you do not leave footprints when you walk on it.

Step 3: Installing the Pool Underlayment

The underlayment protects your pool liner from the ground below. Most kayak pools recommend a foam cove and floor

system. First, install the foam cove around the perimeter of the pool area. This is a triangular piece of foam that sits at the bottom edge where the pool wall meets the floor, preventing the liner from being pinched or stressed. But the cove pieces snugly together, using the adhesive backing or duct tape as needed.

Next, roll out the floor foam or underlayment over the entire sand base. Overlap the seams by a few inches and tape them down flat to prevent shifting. If your kit includes a bottom track or rail, place it on top of the underlayment, perfectly centered on your marked circle. This track holds the bottom of the pool wall in place.

Step 4: Assembling the Pool Wall

The pool wall is the backbone of your kayak pool. This step requires at least two strong, coordinated people. The wall is delivered in a tightly rolled coil. Open the box and lay the rolled wall flat on the ground outside your pool circle. Do not unroll it yet. With a helper, stand the roll on its edge and walk it around the perimeter of the pool, letting the wall unroll into a standing circle inside the bottom track. This is a delicate operation; the steel is strong but can kink if forced.

Once the wall is in a rough circle, walk its entire length into the bottom track. The bottom of the wall has a flange that fits into the track. Use a rubber mallet to gently tap the wall down into the track, ensuring it is fully seated. Now, locate the seam where

the two ends of the wall meet. Use the provided bolts, nuts, and backing plates to bolt the seam together tightly. Start at the top and work your way down. This seam must be perfectly straight and flush.

Step 5: Installing the Top Rails and Uprights

With the wall standing and the seam secured, the pool will look a bit floppy. It needs the support of the top rails and uprights. Begin by placing a top cap or connector over the top edge of the wall at one point. Then, insert the corresponding upright post from the outside of the wall. The upright sits on the ground and is attached to the top cap. Work your way around the pool, installing each upright and the connecting top rail sections. This process gradually pulls the wall into a perfect, rigid circle. Ensure all bolts and screws are tight but do not overtighten and strip the holes. This framework will give your pool its final shape and strength.

Step 6: Laying the Liner

This step requires patience, warm weather, and careful technique. Start by unfolding the liner in the middle of the pool on a sunny day. The sun's warmth makes the vinyl flexible and easier to work with. Do not drag the liner across the ground, as it can snag and tear. Spread the liner out evenly, with the center of

the liner roughly matching the center of the pool floor.

Drape the excess liner over the top of the pool wall. There are typically two types of liners: overlap and beaded. For an overlap liner, simply pull the material evenly over the top edge of the wall. For a beaded liner, you must snap the bead into a channel on the top rail. Ensure the liner is centered by checking that the pattern or seams are symmetrical. If your liner has a pattern, it is crucial to get it straight at this stage. Once positioned, use a pool liner clip or a piece of duct tape every few feet to hold the liner in place on top of the wall.

Step 7: Filling the Pool and Smoothing Wrinkles

Begin filling the pool with water from a garden hose. Place the hose in the center of the pool on a towel or rag to prevent it from scratching the new liner. As the water starts to pool on the floor, you can begin smoothing out wrinkles. Walk on the foam floor carefully, pushing wrinkles toward the walls and out of the pool. The weight of the water will help stretch the liner into place.

Fill the pool with only about one inch of water. At this point, go around the entire perimeter and adjust the liner, pulling it evenly over the wall to remove major creases. Continue filling to about six to eight inches of water. Now is the time to make final adjustments to the liner to eliminate any remaining wrinkles. Once the water depth reaches the bottom of the wall skimmer

opening, you can stop filling to install the skimmer faceplate and gasket.

Step 8: Installing the Skimmer and Return Fittings

Most kayak pools come with a pre-cut hole for the skimmer and return inlets. If not, you will need to carefully cut them out using the template provided. Install the skimmer by placing the gasket from the inside of the pool, then the faceplate, and tightening the screws from the exterior side. Use plenty of silicone sealant on all screws and gaskets to prevent leaks. Do the same for the return inlet fittings. Connect your hoses from the pump to the skimmer and from the return inlet back to the filter outlet. Use hose clamps on all connections to ensure they are watertight.

Step 9: Completing the Final Fill and Trim

Once the skimmer and returns are installed, you can resume filling the pool all the way to the recommended water level, typically up to the middle of the skimmer opening. As the water rises, continue to adjust the liner